

# PURCHASE ORDER

PHILIPPINE STATISTICS AUTHORITY

2/F Martina Sugbo Center, P. Burgos St., Brgy. San Roque, Cebu City

Supplier :	<b>OFFICEBOX ENTERPRISES</b>	P.O. No. : 0722-PO2024-06-053			
Address :	Arcada 5, Tipolo Mandaue City	Date : 6 June, 2024			
TIN :	214-859-198-00000	<b>Mode of Procurement: Small Value Procurement</b>			
Gentlemen: Please furnish this Office the following articles subject to the terms and conditions contained herein:					
Place of Delivery :	2F Martina Sugbo Ctr. P Burgos St. San Roque Cebu City	Delivery Term : Full Delivery per Day			
Date of Delivery :	15-30 working days upon receipt of PO	Payment Term : Within 30 working days after receipt of the billing statement			
Stock/ Property	Unit	Description	Quantity	Unit Cost	Amount
1	lot	PROCUREMENT OF SUPPLY, DELIVERY AND INSTALLATION OF AIRCONDITIONING UNITS FOR PSA CEBU	1	777,500.00	777,500.00
1.1	units	Airconditioning units, 3 tonner, inverter, split type floor mounted, indoor unit	5		599,000.00 (119,800.00/unit)
		Front Panel Color : WHITE			
		Dimension: (HxWxD) - 4,850x620x350(mm)			
		Weight (Mass) - 45kg			
		Capacity Indication - 4.0 HP			
		Rated Cooling Capacity (Min - Max) - 10.0 (5.0 - 11.2 Btu/h			
		Rated Power Consumption - 3.58 kW			
		COP - 2.79 W/W			
		CSPF - 4.12 Wh/Wh			
		DOE Star Rating - 5*			
		Power Supply - 1ct> / 220V / 60Hz			
		Front Panel Color : WHITE			
		Airflow Rate (H/M/L) - 1,200 / 1,905 / 990 CFM			
		Sound Level - 52/49/46 dB(A)			
		Refrigerant:			
		Charge: 0.95kg			
		Connecting Pipes:			
		Liquid Pipe: 09.5mm			
		Gas Pipe: 015.9mm			
		Drainage: 019.15mm			
		Maximum Interunit Piping Length - 50m			
		Minimum Circuit Amps - 25.1A			
		Maximum Fuse Amps: 32A			




1.2	units	Labor and Materials: Dismantling (old Units) and Installation (new units)	7	178,500.00 (25,500/unit)
		Labor: pipe leak testing, flushing, welding and Brazing, System Commissioning and Refrigerant Charging and Dismantling units for replacement and Installation of the new units		
		Materials: supply of new copper piping, indoor and Outdoor Bracket and Accessories, Insulated copper piping, Communication Wiring, refrigerant gas, nitrogen, welding materials, vinyl tape, drain pipe, clips, sealant, breakers and all installation consumables,		
		Warranty: one (1) year parts and labor, five (5) years for compressor		
		Delivery Period P 15-30 working days after the receipt of PO		
		PHILGEPS REGISTRATION		
		MAYOR'S PERMIT		
		Mode of Payment:		
		SEND BILL Arrangement or 15-30 working days after full delivery		
		Price quotation/s validity: Must be valid for a period of thirty (30) calendar days from the date of submission.		

PR#: 0722-2024-05-067 (PSA-CEBU)


Amount in Words:	SEVEN HUNDRED SEVENTY-SEVEN THOUSAND FIVE HUNDRED PESOS ONLY	777,500.00
------------------	--	------------

*In case of failure to make the full delivery within the time specified above, a penalty of one-tenth (1/10) of one percent for every day of delay shall be imposed on the undelivered item/s.*

Conforme:

  
**RICHIE ESPARCA**  
 Signature over Printed Name of Supplier  
 6/10/24  
 Date

Very truly yours,

  
**ARIEL E. FLORENDO**  
 Regional Director  
 07 JUNE 2024  
 Date

01-Regular Fund  
 Fund Cluster : // 07-Trust Fund  
 Funds Available : \_\_\_\_\_  
**SYMPHA S. CHIU**  
 A.O.-1/OIC-Accounting

ORS/BURS No. : \_\_\_\_\_  
 Date of the ORS/BURS: \_\_\_\_\_  
 Amount : \_\_\_\_\_