

Preventive Maintenance for Electrical Panel Boards, Breakers and Insulation Resistance Test for PSA – TAM and CVEA Buildings			
Building	Item Description	Quantity	Unit
	Specification		
TAM	1. Preventive Maintenance of five (5) Electrical/Power Rooms with nineteen (19) sets of panel Boards and breakers (including retightening of electrical termination and connection, cleaning dust and debris)	1	lot
	2. Conduct insulation Resistance Test and Thermal Scanning	1	lot
	3. Provide Test Result and Certification with duly signed of registered electrical Engineer.	1	lot
CVEA	1. Preventive Maintenance of five (5) Electrical/Power Rooms with nineteen (19) sets of panel Boards and breakers (including retightening of electrical termination and connection, cleaning dust and debris)	1	lot
	2. Conduct insulation Resistance Test and Thermal Scanning	1	lot
	3. Provide Test Result and Certification with duly signed of registered electrical Engineer.	1	lot